



NOTE:

1. REMOVE TEMPORARY CONNECTION AT CORPORATION STOP ON EXISTING MAIN AFTER FILLING AND FLUSHING OF NEW MAIN.
2. DO NOT REMOVE TEMPORARY CONNECTION AT CORPORATION STOP ON NEW MAIN UNTIL ALL TESTING HAS BEEN COMPLETED.
3. CONTRACTORS MUST CALL WATER PLANT PH. # (305) 673-7080 BEFORE FLUSHING WATER LINES OR FIRE HYDRANTS.
4. ALL WATER USED FOR FILLING, FLUSHING, AND TESTING SHALL BE METERED AND PAID FOR IN ACCORDANCE WITH PUBLISHED WATER USAGE CHARGES.
5. WATER LINES TO BE CLEANED WITH A SOFT PIG. CONTRACTOR TO REIMBURSE THE CITY FOR RETAKING AND REPROCESSING WATER SAMPLES FOR FAILED TESTS.
6. DOUBLE VALVE SHALL REMAIN IN PLACE AFTER TEST IS COMPLETED.

**FILLING & FLUSHING
CONNECTION
N.T.S.**

F:\work\SALL\CAD-DWG\STANDARDS\CMB_STANDARD_DETAILS\Public Works Manual\CMB Water Details